

- 1. CONTRACTOR TO VERIFY ALL DIMENSIONS. FACTORY CANNOT ASSUME ALTERATION COSTS AFTER FINAL SUBMITTAL DRAWINGS HAVE BEEN APPROVED.
- 2. HOUSING, SIDE ARM TUBES, AND COUNTERWEIGHTS (12 x 12) TO BE HOT DIP GALVANIZED.
- 3. STEEL OPERATOR TO HAVE DOORS IN FRONT AND BACK (ROADWAY AND COUNTERWEIGHT END).
- 4. STEEL BOLLARD TO HAVE DOOR IN BACK.
- 5. GALVANIZED ANCHOR BOLTS & TEMPLATE BY B & B. (Ø1.125-7 UNC X 2'-9" LONG).
- 6. GASKET OR SILICON TO BE PLACED BETWEEN PIVOT PLATE ASSEMBLY & HOUSING TOP PLATE.
- 7. BARRIER ARM TO HAVE MAGLOCK.
- 8. .875" DIAMETER CABLE TO LOOP THROUGH 4" NOM SCH 40 PIPE.
- 9. .188" SS TRUSS CABLES WITH GALVANIZED TURNBUCKLES, 2 PLACES.
- 10. BARRIER ARM TO HAVE RED & WHITE REFLECTIVE STRIPES 16" WIDE
- 11. PRODUCT SHOWN WITH OPTIONAL COMPONENTS INSTALLED.

CR-25E Barrier DIM A = 22'-4''CLEAR OPENING = 20'-0" **B&B ARMR** 2009 Chenault Dr #114 Carrollton, Tx 75006 800-367-0387